



## **Loyalsock Township S.D. Bus Garage Addition** **G.C./E.C. ADDENDUM #6, October 10, 2016**

This Addendum forms a part of the Contract Documents and modifies the original Project Specifications and Drawings dated July 26th, 2016. Bidders shall carefully examine the Project Specifications for revised and updated items.

NOTE: Bidders must acknowledge receipt of this Addendum on their Bid Form.  
Just as a reminder - all bidders are responsible to do a complete review of the entire set

**A. Clarification to Pier footing size and reinforcing requirement**

**1. #5 rebar. 24 inch square. Refer to drawing A-2**

**B. Clarification to concrete floor slab**

**1. There isn't any existing concrete slab in this project no dowels are required, Patch new bituminous pavement uniformly, match and align with the existing.**

**C. Spec. section 08 71 00- Door Hardware is not included in manual. Please provide specification and hardware list for new man doors. The five new doors are to be installed with new 90 minute frame and 1 ½ pair of rated hinges and panic hardware**

**D. the Bid form has been revised, (attached this addenda #6), to include a line for the Add alternate #5, the addition of new CMU work above the West side doors.**

**This concludes Addendum #6**

Please direct any additional questions to Robert Lack @ RAL Architecture + Design  
570.524.2300 or [rlack@ralad.com](mailto:rlack@ralad.com)

